

Project Overview

Spencer to Webster Transmission Project

Need

This project is being proposed to address the condition of the deteriorating 69kV T20 transmission lines and the need to update and maintain system reliability. The project will address ongoing woodpecker damage throughout the entirety of the structures of the transmission line.


Scope

This project includes:

- Replacement of 216 existing wood structures with new, taller, steel structures; Net reduction of 34 structures
- Rebuilding of the existing 69kV line to 115kV standards
- Addressing woodpecker damage, pole deterioration, damaged cross-arms
- Installation of optical ground wire
- Reconfiguration of the current line to be rebuilt in the center of the existing right-of-way

National Grid

Area Overview: Spencer to Webster Transmission Project



Project in Spencer

Total Distance: 4.2 miles

Number of Structures:

Existing: 58


Replaced: 51

Net reduction: 7

Structure Heights:

Existing Average: 50 ft

Proposed Average: 73 ft



Project in Charlton

Total Distance: 8.4 miles

Number of Structures:

Existing: 122


Replaced: 110

Net reduction: 12

Structure Heights:

Existing Average: 53 ft

Proposed Average: 76 ft



Project in Dudley

Total Distance: 3.6 miles

Number of Structures:

Existing: 53


Replaced: 44

Net reduction: 9

Structure Heights:

Existing Average: 54 ft

Proposed Average: 78 ft



Project in Webster

Total Distance: .8 miles

Number of Structures:

Existing: 17


Replaced: 11

Net reduction: 6


Structure Heights:

Existing Average: 50 ft

Proposed Average: 80 ft



Structure Comparison



National Grid ROW Cross-Section – T20

Permitting Process



Energy Facilities Siting Board (EFSB):

- Ensures that projects will provide a reliable energy supply, with a minimum impact on the environment, at the lowest possible cost.
- · Reviews need, alternatives, environmental impacts, costs
- Opportunity for municipal and abutter participation

Environmental Permitting Expected:

- DEP 401 Water Quality Certificate
- Department of Environmental Protection (DEP) Chapter 91 Waterways
- DEP Wetlands Protection Act Order of Conditions
- U.S. Army Corps of Engineers Section 404 General Permit

Local Permitting:

- Municipal Conservation Commissions Wetlands Protection Act Order of Conditions
- Municipal and State Non-Environmental Permitting as required (e.g. DOT, Planning Board, Stormwater etc.)
- Railroad Permitting

Project Schedule*Dates subject to change



Mailed Notifications, Project Website, Local Meetings, and more

Field Assessments: Summer 2023 - Ongoing

Construction Reviews, Environmental Field Work, Land Survey, Access Reviews, Cultural Resource Testing, Soil Borings

Vegetation Management:

Completed Prior to Soil Borings: Ongoing- anticipated completion Summer 2025

Prior to Construction: Fall 2028

Permitting: 2024 to 2028

Includes federal, state and local reviews

Construction and Restoration:

Access Roads/Mowing/Matting: April 2029–July 2029

Line Construction: July 2029 - October 2031

Restoration/Pole Removal: October 2031 – March 2032

Thank You

For more information on the Spencer to Webster Transmission Project (T20 Line ACR), please visit or reach our Project Engagement team at:

Dedicated Project Hotline: (800) 454-9601 ext. 1

Email: info@t20project.com

Website: centralmasstransmissionimprovementprojects.com

